FORTA PRO

WE BUILD MODULAR













ABOUT FORTA PRO







- Forta PRO offers prefabricated volumetric modular solutions for:
 - Hospitals and clinics
 - Apartments
 - Student and Workers dormitories
 - Hotels and more...
- Authorized supplier to Danish hospitals
- Experienced in medical design
- Implemented projects in Denmark, Sweden, Iceland, UK, USA, Norway, Latvia
- 120 000 m2 per annum capacity
- Worldwide shipping

IDENTIFICATION





MODULAR ICU CLINIC

MANUFACTURER Forta Prefab SIA, company No 40103727283

CERTIFICATES

Quality Management, Environmental Management, Occupational Health and Safety Management Systems of Forta Prefab Ltd. are ISO 14000, ISO 50001, ISO 45001 and ISO 9001 certified: http://www.fortapro.com/certificates/

IDENTIFICATION



DISCLAIMER

- The illustrations in this document are all subject to changes and amendments.
- If the build-up and dimensions should be amended during the design detailing phase, any such amendments may impact the price.
- All dimensions are in millimetres
- This drawing is a copyright and property of Forta PRO and is not to be produced, copied, handed over to third party or used for any other purpose other than for which it is intended.
- All dimensions shall be verified on site prior to start of work. Any discrepancy shall be brought to the notice of Forta PRO.
- The construction manager/ contractor must check all dimensions and details and be responsible for the same.
- Dimensions are to be read and not to be scaled.
- This drawing is to be read in conjunction with all relevant architectural, structural, MEP drawings, specialist drawings along with their specifications.
- Any discrepancy shall be brought to the notice of the consultants within 7 working days of receipt of this drawing,
- but always prior to procurement/ execution of works.
- Drawing approval is for the conformity with outline design intent only and does not relieve the project managers/ contractors/ sub contractors from full responsibility for the accuracy, integration and fitness for purpose of design.
- Project managers to revert back within 7 working days of receipt, of this drawing on co-ordination and buildability issues. If
 otherwise, it would be deemed that they have understood and accepted the drawings/ design and own full responsibility for
 the works carried out accordingly.
- Optional items are not included in the price.

DESCRIPTION





FREE STANDING MODULAR FAST DEPLOYMENT 20-BED ICU BLOCK WITH TECHNICAL FACILITIES

This 20-bed intensive care unit (ICU) department block is supposed to be placed on site-build or prefabricated foundations (not included in the modular program) and connected to hospital systems (ventilation, heating, medical gas, electrical, HIS etc.).

All mechanical, electrical, plumbing, heating, ventilation, air conditioning, medical gas system distribution components up to terminal units are factory installed in the module. Fixed medical equipment can be included and factory installed (not included in the given modular program). The module is ready for plug-and-play functionality.

GENERAL NOTES AND EXCLUSIONS



- All proposed details are indicative only!
- All the details need to be addressed during the design phase!
- All sizes adjustable/alterable for modular design, construction and transportation!
- All potential risks and procedures to eliminate them should be evaluated during design phase!
- During the project, all standards and their application must be evaluated!
- It is possible to reduce module types by making all floor heights identical!

- Architectural, engineering and other specifications/details will be developed during the design phase
- Shafts and utility points should be considered during the design phase
- Structural solutions will be developed during the design phase
- Facade structure and finishing is excluded
- Areas other than marked as MODULAR are not included, if not specified otherwise
- All specifications and documents shall be made available to producer in plain English
- Explicit information on accessibility- or any other specific requirements should be provided to FORTA PRO in the initial design stage. Such as, but not limited to room sizes, special accessibility equipment installation, floor slopes, lighting, door opening sizes
- Gross modular area is defined excluding facade layers (assumed 110mm in thickness)

FIRE: EI 60

	lodular Area osed type IC	
Name	Number	Area
ICU 01.1	01.1-001	49.91 m²
ICU 01.1	01.1-002	49.91 m²
ICU 01.1	01.1-003	49.91 m²
ICU 01.1	01.1-004	49.91 m²
ICU 01.2	01.2-001	49.91 m ²
ICU 01.2	01.2-002	49.91 m²
ICU 01.2	01.2-003	49.91 m²
ICU 01.2	01.2-004	49.91 m²
ICU 02.1	02.1-001	60.22 m ²
ICU 02.2	02.2-001	63.43 m²
ICU 03.1	03.1-001	52.57 m²
11		575.46 m ²

ICU-03.1	ICU-01.1	ICU-01.2	ICU-01.1	ICU-01.2	ICU-01.1	ICU-01.2	ICU-01.1	ICU-01.2	ICU-02.1	ICU-02.2

PROJECT NAME:		PROJECT Nº:	
Respiratory ICU		20EU-M003	
SHEET NAME:		REVISION:	
ICU	department plan		
DRAWING ID:		SCALE:	
	A100 /	1:200	@A3
PROJ. MAN.	Ethan Chetrit	STAGE:	
APPROVED BY	Kristaps Miķelsons	Estimation	
ARCHITECT	Mārcis Rancāns		
DRAWN BY	Mārcis Rancāns		
REVIEW DATE	26/03/2020 15:26:35		
PROJECT ISSUED	Issue Date		

FORTA PRO

W E B U I L D M O D U L A R SIA Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

26	Revision	Date	Description	Issued by
/03/20				
720				
020				
5				
:28				

1) All dimensions are in milimeters. 2) This drawing is a copyright and property of Forta PRO and is not to be produced, copied, handed over to third party or used for any other purpose other than for which it is intended. 3) All dimensions shall be verified on site prior to start of work. Any discrepancy shall be brought to the notice of Forta PRO. 4) The construction manager/contractor must check all dimensions and details and be responsible for the same. 5) Dimensions are to be read and not to be scaled. 6) This drawing is to be read in conjunction with all relevant architectural, structural, MEP drawings, specialist drawings along with their specifications. 7) Any discrepancy shall be brought to the notice of the consultants within 7 working days of receipt, of this drawing is vested in "Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

SIA Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

The Copyright in this drawing is vested in "Forta Pro" and no license or assignment of any kind has been, or is granted to any third party whether by provision of copies or originals, or otherwise agreed in writing. Electronic Data / drawings are issued as "read only" and should not be interrogated for measurement.

FIRE: EI 60

dosed type ICO				
Name	Number	Area		
ICU 01.1	01.1-001	49.91 m²		
ICU 01.1	01.1-002	49.91 m ²		
ICU 01.1	01.1-003	49.91 m²		
ICU 01.1	01.1-004	49.91 m²		
ICU 01.2	01.2-001	49.91 m²		
ICU 01.2	01.2-002	49.91 m²		
ICU 01.2	01.2-003	49.91 m²		
ICU 01.2	01.2-004	49.91 m²		
ICU 02.1	02.1-001	60.22 m²		
ICU 02.2	02.2-001	63.43 m²		
ICU 03.1	03.1-001	52.57 m²		
11		575.46 m²		

Gross Modular Area (GMA)

Net Internal Area (NIA) in ICU-01.1 Number Name Area Perimeter 13.78 m 3.48 m

WIDTH*:4400 mm HEIGHT*:4106 mm LENGTH*:11368 mm WEIGHT**:17.51 t

*Structural elements are not taken into account **Indicative and for information only.

	PROJECT NAME:		PROJECT Nº:	
	Res	spiratory ICU	20EU-M003	
	SHEET NAME:		REVISION:	
	ICU-01.1 /	floor plan - architecture	X	
	DRAWING ID:		SCALE:	
		A101 / X	1:50	
	PROJ. MAN.	Ethan Chetrit	STAGE:	
	APPROVED BY	Kristaps Miķelsons	Estimation	
ARCHITECT DRAWN BY REVIEW DATE		Mārcis Rancāns		
		Mārcis Rancāns		
		26/03/2020 15:26:35		
	PROJECT ISSUED	Issue Date		

FORTA PRO

SIA Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

The Copyright in this drawing is vested in "Forta Pro" and no license or assignment of any kind has been, or is granted to any third party whether by provision of copies or originals, or otherwise agreed in writing Electronic Data / drawings are issued as "read only" and should not be interrogated for measuremer

2020.03.23 first draft Description

1) All dimensions are in milimeters. 2) This drawing is a copyright and property of Forta PRO and is not to be produced, copied, handed over to third party or used for any other purpose other than for which it is intended. 3) All dimensions shall be verified on site prior to start of work. Any discrepancy shall be brought to the notice of Forta PRO. 4) The construction manager/ contractor must check all dimensions and details and be responsible for the same. 5) Dimensions are to be read and not to be scaled. 6) This drawing is to be read in conjunction with all relevant architectural, structural, MEP drawings, specialist drawings along with their specifications. 7) Any discrepancy shall be brought to the notice of the consultants within 7 working days of receipt of this drawing, but always prior to procurement/ execution of works. 8) Drawing approval is for the conformity with outline design intent only and does not relieve the project managers/ contractors/ sub contractors from full responsibility for the accuracy, integration and fitness for purpose of design. 9) Project managers to revert back within 7 working days of receipt, of this drawing on co-ordination and Issued by buildability issues. If otherwise, it would be deemed that they have understood and accepted the drawings/ design and own full responsibility for the works carried out accordingly.

Gross Modular Area (GMA) closed type ICU

49.91 m² 49.91 m² 49.91 m² 49.91 m² 60.22 m² 63.43 m² 52.57 m² Electrical and Medical gas 010 supply panel, wall mounted Patient room ICU Corridor Patient room ICU Air-lock 10.98 m² 16 76 m² 9 22 m² 16₁02 m² ICU bed 1 1/2 leaf door. Window for visual control Nurse work-desk to be finished on-site Nurse has 0.67 m²

Electrical and Medical gas supply panel:

3x - ventilator, flowmeter pipeline, anesthetic machine

Air 2x - ventilator

Suction 2x - suction apparatus, endoscopy

24x - bed, ventilator, multi parameter monitor, 4-9x infusion pump,

4x syringe pump, computer, examination lamp, blood warmer, ecg, eeg, us/cardiac-echo, endoscopy, anaesthetic machine,

haemofiltration/ haemodialysis, +redundant outlets 16x - equipotential earth connector plugs

GND RCD 1x - residual current device for sockets

Data 2x - computer, CCTV

Wall supplies:

8x - electric fan, humidifier, defibrilator, x-ray,

vacuum cleaner, +redundant outlets

RCD 1x - residual current device for sockets

2x - CCTV, computer Data

1x - Staff/staff call, cardiac arrest call + audio-visual signal elements Nurse call:

Nurse work-desk:

3x - computer, telephone, +redundant outlet GPO

2x - computer, telephone Data

Surface cleaning:

All surface materials be compatible with hard cleaning with disinfectants containing:

Description

- Hydrogen Peroxide
- Sodium Hypochlorite
- Isopropanol
- Formaldehyde
- Glutaraldehyde
- Peracetic acid

Room Material and outline specifications:

Vinyl/ Linoleum flooring, slip resistant, 150mm coving, Floor

Paint, chemically resistant to daily wet cleaning with Walls

disinfectants

Ceiling Ceiling tiles, accoustically absorbent, sealed

Door: ICU 1 1/2 hinged door, clear opening 920+480mm, air tight

Door protection 300mmH kick plate, vinyl 1000Wx800H mm wall opening, with integrated blinds Window: control

Window: exterior

1800Wx1600H mm wall opening, transparent from inside, translucent from outside

laminate

Worktop

Other Fixtures, Equipment and associated Services:

Notes:

Humidity

No RO water and sewage provisioned for haemodialysis Haemodialysis

Examination light Assumed fixed on wall panel rail

Services not provisioned for bariatric patients Bariatric Columns Column dimensions w/out fire paint thickness

Mechanical ventilation and cooling, Air supply:ICU arrestance 85% (F7 according to EN 1822:2009), min. 10 AC/hr

Mechanical ventilation and cooling, Air supply:isol.

arrestance 85% (F7 according to EN 1822:2009), min. 15 AC/hr

Emergency power No special emergency power outlets are provisioned Temperature Locally controllable

Low Pressure Hot Water radiators, thermostatically controllable Heating

Lighting Diffuse, reading and examination lighting

Locally controllable

1) All dimensions are in milimeters. 2) This drawing is a copyright and property of Forta PRO and is not to be produced, copied, handed over to third party or used for any other purpose other than for which it is intended. 3) All dimensions shall be verified on site prior to start of work. Any discrepancy shall be brought to the notice of Forta PRO. 4) The construction manager/ contractor must check all dimensions and details and be responsible for the same. 5) Dimensions are to be read and not to be scaled. 6) This drawing is to be read in conjunction with all relevant architectural, structural, MEP drawings, specialist drawings along with their specifications. 7) Any discrepancy shall be brought to the notice of the consultants within 7 working days of receipt of this drawing, but always prior to procurement/ execution of works. 8) Drawing approval is for the conformity with outline design intent only and does not relieve the project managers/ contractors/ sub contractors from full responsibility for the accuracy, integration and fitness for purpose of design. 9) Project managers to revert back within 7 working days of receipt, of this drawing on co-ordination and buildability issues. If otherwise, it would be deemed that they have understood and accepted the drawings/ design and own full responsibility for the works carried out accordingly.

Number

Corridor

Net Internal Area (NIA) in ICU-02.1					
Name	Department	Area	Perimeter		
om ICU	ICU-02.1	16.02 m²	15.80 m		
	ICU-02.1	10.98 m²	13.78 m		
e	ICU-02.1	0.67 m²	3.48 m		
	ICU-02.1	9.22 m²	12.78 m		
om ICU	ICU-02.1	16.76 m²	16.38 m		
	·	53.65 m²			

WIDTH*:4400 mm HEIGHT*:4106 mm LENGTH*:13718 mm WEIGHT**:21.13 t


*Structural elements are not taken into account **Indicative and for information only

PROJECT NAME:		PROJECT Nº:	
Re	20EU-M003		
SHEET NAME:		REVISION:	
ICU-02.1 /	floor plan - architecture		
DRAWING ID:		SCALE:	
	A102 /	1:50	@A3
PROJ. MAN.	Ethan Chetrit	STAGE:	
APPROVED BY	Kristaps Miķelsons	Estimation	
ARCHITECT	Mārcis Rancāns		
DRAWN BY	Mārcis Rancāns		
REVIEW DATE	26/03/2020 15:26:36		
PROJECT ISSUED	Issue Date		
		·	

FORTA PRO

SIA Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

The Copyright in this drawing is vested in "Forta Pro" and no license or assignment of any kind has been, or is granted to any third party whether by provision of copies or originals, or otherwise agreed in writing Electronic Data / drawings are issued as "read only" and should not be interrogated for measuremer



Description

FORTA PRO

SIA Forta Pro, Rīga, Emiļa Melngaiļa iela 1A, LV-1010

The Copyright in this drawing is vested in "Forta Pro" and no license or assignment of any kind has been, or is granted to any third party whether by provision of copies or originals, or otherwise agreed in writing.

Electronic Data / drawings are issued as "read only" and should not be interrogated for measurement.

Gross Modular Area (GMA) closed type ICU

Number Area

49.91 m² 60.22 m² 63.43 m² 52.57 m²

575.46 m

Area Perimeter

9.00 m 6.60 m 9.13 m 10.93 m

PROJECT Nº:

20EU-M003

REVISION:

SCALE:

1:50

STAGE:

Estimation

MEDICAL EQUIPMENT





OPTIONAL MEDICAL EQUIPMENT::

20 pcs. ICU bed

60 pcs. O₂ flowmeter

20 pcs. Wall bedhead panel / Ceiling pendant

20 pcs. Ventilator, adult/neonatal

40 pcs. Suction regulator

5 pcs. Defibrillator, portable

120 pcs. Infusion pump

20 pcs. Multiparameter monitor

(ECG, temperature, BP, O₂/CO₂, CVP, etc.)

80 pcs. Syringe pump

20 pcs. Examination lamp

20 pcs. EEG

1 pcs. Diagnostic ultrasound system

1 pcs. Endoscopy/Bronchoscopy system

2 pcs. Anaesthetic machine

4 pcs. Hemofiltration machine

10 pcs. Nurse information centre system

20 pcs. Video laryngoscope



www.fortapro.com

Jurkalnes Street 15/25 - 221, Riga, Latvia LV-1046

CONTACT US +371-67-32-32-34 info@fortapro.com

Facebook.com/FortaPRO



